

New Administrative Building, Near Akurdi Railway Station, Pune – 411044. Pune Metropolitan Region Development Authority, Pune नवीन प्रशासकीय इमारत, आकुर्डी रेल्वे स्टेशन जवळ, पुणे.-४११०४४ पुणे महानगर प्रदेश विकास प्राधिकरण, पुणे



Ph No. : 020-27659855 फोन नं. ๑२๑-२७६५९८५५ Email: sezpmrda@gmail.com ce2wssd@gmail.com

कोटेशन नोटीस

प्राप्त करणे कामी अशा प्रकारची काम करणा−या ठेकेदार /पुरवठा करणा−या कडुन दि .<u>०४/०८</u> /२०२५ ते दि . <u>७२</u>/ <u>०</u>८ २०२५ चे कालावधीमध्ये सिलबंद दरपत्रक /कोटेशन विविध प्रकारची कामे करणेत येत आहेत. ही कामे करण्यासाठी /अंदाजपत्रक करणे करीता खालील बार्बीच्या कामासाठी तपशिला प्रमाणे बाजार भाव (Market Rate) मागविणेत येत आहे. पुणे महानगर प्रदेश विकास प्राधिकरणाच्या कार्यक्षेत्रात अभियांत्रिकी विभाग २ मार्फत पवना नदीसाठी तात्पुरती प्रदूषण नियंत्रण उपाययोजना करणे <mark>या प्रकल्पामध्ये</mark>

कोटेशन नोटीस क्र. -PMRDA/Pavana/ ०५/2025-26

Barricades On Bridge:- Supply, design, and install durable fabricated barricades up to 3 m high from the bridge slab along both edges of the Pavana River bridges in the PMRDA area—according to approved design-drawing intent—with all necessary accessories (brackets, hardware, fasteners, etc.) included. The barricades shall be designed to withstand a wind pressure of 56 kg/m² per IS 875 Part III, with proof testing at 1.5× the design wind load. Fabrication shall use IS 2062 Fe 410 structural steel—comprising channels, flats, and uprights—shop-fabricated via precision cutting, drilling, welding, or high-strength bolting in strict compliance with IS 800 workmanship standards. All steel surfaces shall receive a high-grade anti-corrosive paint system (surface preparation, primer, and topcoat) for outdoor resilience. The barricade line will consist of modular segments approximately 2.5 m wide, aligned and interconnected by robust upright posts employing factory-fitted interlocking spigot-and-socket joints or site-welded seamless connections, ensuring structural continuity, rigidity, and ease of installation or replacement. Each	No.	Product Descriptions	Product Image	Qty	Unit
intent—with all necessary accessories (brackets, hardware, fasteners, etc.) included. The barricades shall be designed to withstand a wind pressure of 56 kg/m² per IS 875 Part III, with proof testing at 1.5× the design wind load. Fabrication shall use IS 2062 Fe 410 structural steel—comprising channels, flats, and uprights—shop-fabricated via precision cutting, drilling, welding, or high-strength bolting in strict compliance with IS 800 workmanship standards. All steel surfaces shall receive a high-grade anti-corrosive paint system (surface preparation, primer, and topcoat) for outdoor resilience. The barricade line will consist of modular segments approximately 2.5 m wide, aligned and interconnected by robust upright posts employing factory-fitted interlocking spigot-and-socket joints or site-welded seamless connections, ensuring structural continuity, rigidity, and ease of installation or replacement. Each	_	Barricades On Bridge: Supply, design, and install durable fabricated barricades up to 3 m high from the bridge slab along both edges of the Pavana River bridges in the PMRDA area—according to approved design-drawing		8800	Sqm.
56 kg/m² per IS 875 Part III, with proof testing at 1.5× the design wind load. Fabrication shall use IS 2062 Fe 410 structural steel—comprising channels, flats, and uprights—shop-fabricated via precision cutting, drilling, welding, or high-strength bolting in strict compliance with IS 800 workmanship standards. All steel surfaces shall receive a high-grade anti-corrosive paint system (surface preparation, primer, and topcoat) for outdoor resilience. The barricade line will consist of modular segments approximately 2.5 m wide, aligned and interconnected by robust upright posts employing factory-fitted interlocking spigot-and-socket joints or site-welded seamless connections, ensuring structural continuity, rigidity, and ease of installation or replacement. Each		intent—with all necessary accessories (brackets, hardware, fasteners, etc.) included. The barricades shall be designed to withstand a wind pressure of			
flats, and uprights—shop-fabricated via precision cutting, drilling, welding, or high-strength bolting in strict compliance with IS 800 workmanship standards. All steel surfaces shall receive a high-grade anti-corrosive paint system (surface preparation, primer, and topcoat) for outdoor resilience. The barricade line will consist of modular segments approximately 2.5 m wide, aligned and interconnected by robust upright posts employing factory-fitted interlocking spigot-and-socket joints or site-welded seamless connections, ensuring structural continuity, rigidity, and ease of installation or replacement. Each		56 kg/m ² per IS 875 Part III, with proof testing at 1.5× the design wind load. Fabrication shall use IS 2062 Fe 410 structural steel—comprising channels.			
preparation, primer, and topcoat) for outdoor resilience. The barricade line will consist of modular segments approximately 2.5 m wide, aligned and interconnected by robust upright posts employing factory-fitted interlocking spigot-and-socket joints or site-welded seamless connections, ensuring structural continuity, rigidity, and ease of installation or replacement. Each		flats, and uprights—shop-fabricated via precision cutting, drilling, welding, or high-strength bolting in strict compliance with IS 800 workmanship standards.			
consist of modular segments approximately 2.5 m wide, aligned and interconnected by robust upright posts employing factory-fitted interlocking spigot-and-socket joints or site-welded seamless connections, ensuring structural continuity, rigidity, and ease of installation or replacement. Each		All steel surfaces shall receive a high-grade anti-corrosive paint system (surface preparation, primer, and topcoat) for outdoor resilience. The barricade line will			
spigot-and-socket joints or site-welded seamless connections, ensuring structural continuity, rigidity, and ease of installation or replacement. Each	***************************************	interconnected by robust upright posts employing factory-fitted interlocking			
		spigot-and-socket joints or site-welded seamless connections, ensuring			

Zo.	Product Descriptions	Product Image	Qty	Unit	(Excluding GST)
	1117				
	PVC—affixed at eye level, displaying bilingual warning text "Fine (municipal				
	penalty applicable) for throwing waste from the bridge," with signage spaced				
	every 5 m to effectively deter littering. COST excludes cost of				
	SCAFFOLDING, or any kind of staging required if any. Including				
	transportation, loading, unloading and all other taxes excluding GST				

अटी व शर्ती –

- १ . इच्छुक ठेकेदारांनी उपरोक्त तक्त्यात नमूद केलेल्या साहित्याचे दिलेल्या Specification सह सीलबंद कोटेशनचे पाकीट मा .अधीक्षक अभियंता , अभियांत्रिकी विभाग मजला, नवीन प्रशासकीय इमारत, आकुर्डी रेल्वे स्टेशन जवळ, आकुर्डी, पुणे.४११०४४ येथे समक्ष अथवा<u>ce2pmrda@gmail.com</u>या इमेल आयडीवर दरपत्रकदेण्यातयावेत. २, पुणे महानगर प्रदेश विकास प्राधिकरण, पुणेयांचे नावे दि.<u>०४/०८</u>/२०२५ ते दि. *9<u>9</u> / <u>ग्८</u>/२०२५*पर्यंत ३.०० वाजेपर्यंत अभियांत्रिकी विभाग २, ५ रा ce 2 wssd @gmail. com
- २. साहित्याचे दरइतर सर्व करासहित (GSTवगळुन) देणेत यावे.
- ३. सिलबंद कोटेशन पाकिटावर कोटेशन नोटीस क्र., कामाचे नांव तसेच फर्म /कंपनीचा नावाचा स्पष्ट उल्लेख करावा.
- ४ . अटीयुक्त, उशिरा आलेल्या व अपूर्ण कोटेशनचा विचार केला जाणार नाही .
- ५. ठेकेदारास / एजन्सीस त्याची फर्म अस्तित्वात असलेबाबतचा पुरावा मागणी अंती सादर करावा लागेल.
- ६ . अशा प्रकारची कामे करत असल्याचा पुरावा मागणी अंती सादर करावा लागेल .
- ७. सदरची कोटेशन नोटीस https://www.pmrda.gov.in/downloads/notification-circulars/ या वेबसाईटवर पाहणेस उपलब्ध आहे.

जा.कजा.क.६०९५४ गण्डि/२०२५/प्र.क.८८/ १४२१ /२०२५ दिनांकः- १४ /०८/२०२५

अधिक अभियंता , अभियांत्रिकी विभाग २ अभियांत्रिकी विभाग २ पुणे महानगर प्रदेश विकास प्राधिकरण, पुणे

प्रतः माहिती तंत्रज्ञान विभाग, पुणे महानगर प्रदेश विकास प्राधिकरण, पुणे यांना वेब साईटवर प्रसिद्धीकामी

BARRICADES ON BRIDGE G.I.CHAINLINK SIZE 50x50MM, Existing Abutment **Existing Abutment**