पुणे महानगर प्रदेश विकास प्राधिकरण, पुणे

Pune Metropolitan Region Development Authority, Pune

नविन प्रशासकीय इमारत, आकुर्डी रेल्वे स्टेशन जवळ, आकुर्डी, पुणे – 411 044

New administrative Building, Near Akurdi Railway Station, Akurdi, Pune - 411 044 फोन क्र.:- 020-25933344/ 27652934 ई-मेल .:comm@pmrda.gov.in

पुणे महानगर नियोजनबद्ध विकास

स्वातंत्र्याचा अमृत महोत्सव

जा. क्र. /EG-2/Electrical Work/संचिका क्र. 120/794/2026 दि. 02/11/2026

दरपत्रक सुचना क्र. 26 /2026-27

पुणे महानगर प्रदेश विकास प्राधिकरण कार्यालयामार्फत पेठ क्र. 12 येथील गृहप्रकल्प 3, 4 व 5 येथे गृहप्रकल्प उभारणीचे काम प्रगतीपथावर आहे. उपरोक्त गृहप्रकल्पातील संपुर्ण पार्किंगच्या किमान 30% जागा ही Electrical Vehicle Charging Points करीता उपलब्ध करून द्यावयाची आहे. त्याअनुषंगाने सदर कामाच्या Non CSR बाबींचे दर निश्चित करणे प्राधिकरण कार्यालयामार्फत प्रस्तावित आहे. सदर दर प्राप्त झालेनंतर उपरोक्त बाबींच्या दरांचे Rate Analysis (दर पृथ्थकरण) करण्यात येणार आहे. सदर कामाचा Non CSR बाबींचा तपशील सोबत जोडण्यात येत आहे.

विषयांकित कामाकरीता इच्छुक कंत्राटदारांनी सिलबंद दरपत्रके पुणे महानगर प्रदेश विकास प्राधिकरणाच्या आकुर्डी कार्यालयाच्या नवीन प्रशासकीय इमारतीतील दुसऱ्या मजल्यावरील अभियांत्रिकी विभाग (रस्ते) येथील आवक कक्षात दि. 13/11/2026 रोजी सायंकाळी 5:00 वाजपर्यंत आवक विभागात देण्यात याव्यात.

अटी व शर्ती-:

1. कोणतेही दरपत्रक मान्य अथवा नाकारण्याचा अधिकार मा. महानगर आयुक्त, पु.म.प्र.वि.प्रा. यांनी राखुन ठेवला आहे.
2. सदर दरपत्रके केवळ दर निश्चित करणेकरीता मागविण्यात येत आहे.
3. नमुद रक्कम ही सर्व करासह (मात्र GST वगळून) असावी.
4. विषयांकित कामाच्या अधिक माहितीकरीता श्री. प्रशांत सावंत, कनिष्ठ अभियंता, अभियांत्रिकी विभाग-2 यांचेशी संपर्क साधावा.
5. ठेकेदार/कंत्राटदार यांनी दरपत्रकासोबत GST व PAN कार्डची पत्र सादर करणे आवश्यक आहे.

सोबत:- Non CSR बाबींचा तपशील.

सही/-
(अभिमान भोसले)
कार्यकारी अभियंता
अभियांत्रिकी विभाग (विशेष प्रकल्प)
पुणे महानगर प्रदेश विकास प्राधिकरण

A) **2W Chargers: AC Charger 1.1*3 kW**

Sr No	Description	Specification	Est Qty	Unit	Rate without GST (Rs.)	Amount (Rs.)
A	**2W Chargers: AC Charger 1.1*3 kW**					
1	**INPUT**		1	No		
	Input Supply	Three phase 415V AC1				
	Input Frequency	50 Hz				
	Input Wires	5 wires – L1, L2, L3, N and PE				
2	**OUTPUT**					
	No. of Output Connectors	3 Sockets				
	Power Output	5A / 1.1 kW Max. per output				
	Output Connector Type	M Type Socket				
3	**USER INTERFACE**					
	SIM Slot	General size SIM card for GSM connectivity				
	Push Button	Push button for Emergency Stop				
	LED Indication	LED indication for charging status				
4	**COMMUNICATION**					
	EVSE to Server	OCPP 1.6				
	Cloud Connectivity	Wi-Fi and Sim Card				
	User Authentication	RFID Enabled, Mobile App				
5	**SAFETY AND PROTECTION**					
	Safety Measures	Emergency Stop Button with Auto Release Function				
	Protection	Over voltage, under voltage, over current, short circuit, surge protection, over temperature, ground fault, residual current				
	Earth(ground)fault protection	Leakage current < 30 mA				
6	**ENVIRONMENTAL**					
	Operating Temperature	0°C to +55°C				
	Operating Humidity	5% to 95% relative humidity, non-condensing				
7	**MECHANICAL**					
	Material	Plastic or Metal Enclosure				
	Cooling	Natural Air Cooled				
	Mounting Type	Wall Mount, Pole Mount				
	IP Rating	IP54 or Higher				
8	**COMPLIANCE & CERTIFICATION**					
	Standard	BEVC-AC001				
	Certification	ARAI				

B) **4W Chargers: DC Charger 60 kW CCS2 with Dual Gun**

Sr No	Description	Specification	Est Qty	Unit	Rate without GST (Rs.)	Amount (Rs.)
B	**4W Chargers: DC Charger 60 kW CCS2 with Dual Gun**					
1	**INPUT**		1	No		
	Input supply	3 phase 400 - 415V AC (+6% and -10%) with 3P+N+PE				
	Input current	Max. 125A				
	Input frequency	45~65 Hz				
	Power factor	0.99 at Nominal Input with Full Load				
2	**OUTPUT**					
	Number of output Guns	2				
	DC output voltage	150 to 1000V				
	Max Output current	125A Per Gun				
	Power output	60KW				
	Charging Cable Length	5 Mtr for Both guns				
	Output efficiency	95% at Nominal Power				
	Output connector type	CCS2				
3	**USER INTERFACE**					
	Display	7” LED with Touch Screen				
	SIM slot	General size SIM card for GSM connectivity				
	LED indication	Multicolor LED indication for charging status				
4	**COMMUNICATION**					
	EVSE to Sever	OCPP 1.6J				
	Cloud connectivity	WiFi,4G				
	User authentication	RFID enabled				
	EVSE to vehicle	CAN Bus/ RS485				
5	**SAFETY AND PROTECTION**					
	Safety measures	Emergency stop button				
	Protection	Over current, Under voltage, Over voltage, Residual Current, Surge protection, short circuit, Over temperature, Ground fault, Communication failure, Insulation monitoring, Residual protection, Smoke Detector and Door Open Alarm.				
	Earth (Ground fault protection)	Leakage current<30mA				
6	**ENVIRONMENTAL**					
	Operating	-20 to 55°C				

Sr No	Description	Specification	Est Qty	Unit	Rate without GST (Rs.)	Amount (Rs.)
	temperature					
	Operating humidity	5 to 95%, non-condensing				
7	**MECHANICAL**					
	Material	MS-CRCA				
	Cooling	Air Cooled				
	Mounting type	Floor mounting				
	IP rating	IP54				
8	**COMPLIANCE & CERTIFICATION**					
	Standard	CCS2:IEC61851, ISO 15118				
	Certificate	ARAI Minimum 60kW or Above rating certificate is also acceptable				